

Formular F3

OBIECTIV: 013 REABIL CENTR MEDIC DARMANESTI

LISTA

cu cantitatile de lucrari pe categorii de lucrari

Obiectul: 2 LUCRARI DE INSTALATII

Categoria de lucrari: 1 INSTAL SANIT INT SI CANALIZARE

Executanti02	Obiectiv013	Obi2	Cate1			[ron]
Nr. crt.	Capitolul de lucrari Simbol Denumire resursa Observatii Corectii Liste anexe	U. M.	Cantitatea	Pretul unitar a) materiale b) manopera c) utilaj d) transport Total(a+b+c+d)	Valoare	

SECTIUNE TEHNICA

SECTIUNE FINANCIARA

0	1	2	3	4	5
---	---	---	---	---	---

1 TSA02XB 91 M CUB 30,00000

SAPATURA MANUALA DE PAMINT IN SPATII LIMITATE, AVIN
D SUB 1,00 M LA CANALIZARE EXTERIOARA

2 00605A2 02 BUCATA 20,00000

TEAVA PVC CU MUFA SI GARNITURA PT.CANALIZARE EXTER
IOARA GRAVITATIONALA D = 110 MM, L = 2 M

L:LA006F1-0043:8815057 -TEAVA PVC CU MUFA SI GARNIT. SN4/SDR41 D=110X3,2MM L=2M

3 00605A1 02 BUCATA 10,00000

TEAVA PVC CU MUFA SI GARNITURA PT.CANALIZARE EXTER
IOARA GRAVITATIONALA D = 110 MM, L = 1 M

L:LA006F1-0122:8816543 -TEAVA CANAL PVC MULTISTRAT CU MUFA D.110X 3,2MM SN4 L1M

4 ACE08A1 82 M CUB 7,00000

UMPLUTURA IN SANT.LA COND.DE ALIM.CU APA SI CANALI
ZARE CU: NISIP §

5 TSD01A1 82 M CUB 23,00000

IMPRASTIEREA CU LOPATA A PAMINTULUI

6 TSD04A1 82 M CUB 20,00000

COMPACTAREA CU MAI.DE MINA A UMPLUT.EXECUT.PE STRA
T.CU UDAREA FIEC.STRAT DE 10CM GROS.T.NECOZIV

7 EA10C1 82 M 65,50000

TEAVA PVC TIP U MONTATA INGROPAT IN PARDOSEALA CU
D=50MM

8 00614A02A 02 BUCATA 15,00000

TUB PP /TRIPLUS CU 1 MUFA SI GARNITURA PT.CANALIZA
RE INTERIOARA D. 40 MM, L =1M

L:LA006T2-0004:8810013 -TUB PP CU 1 MUFA D. 40 MM; L= 1000 MM

Executanti02	Obiectiv013	Obi2	Cate1							ron
0	1	2	3	4	5					
9	00614A02B	02	BUCATA							5,00000

TUB PP /TRIPLUS CU 1 MUFA SI GARNITURA PT.CANALIZA
RE INTERIOARA D. 40 MM, L =2M

L:LA006T2-0006:8810015 -TUB PP CU 1 MUFA D. 40 MM; L= 2000 MM

10	SB17E1	82	BUCATA							31,00000
----	--------	----	--------	--	--	--	--	--	--	----------

COTURI PVC-U, PT.CANALIZARE, CU IMBINARE PRIN LIPIRE
LA 45;67 1/2;87 1/2 GRADE, AVIND D=110 MM

11	6712265		BUCATA							15,00000
----	---------	--	--------	--	--	--	--	--	--	----------

COT PVC TIP U LA 45 GRADE DN 110 NII 2167

12	6712332		BUCATA							8,00000
----	---------	--	--------	--	--	--	--	--	--	---------

COT PVC TIP U LA 67 GR.30M DN 110 NII 2167

13	6712409		BUCATA							8,00000
----	---------	--	--------	--	--	--	--	--	--	---------

COT PVC TIP U LA 87 GR.30M DN 110 NII 2167

14	SB17E1	82	BUCATA							12,00000
----	--------	----	--------	--	--	--	--	--	--	----------

COTURI PVC-U, PENTRU SCURGERE , AVIND D=110 MM

15	8810137		BUCATA							6,00000
----	---------	--	--------	--	--	--	--	--	--	---------

COT PP D. 110 MM; 15 GRD

16	8810138		BUCATA							6,00000
----	---------	--	--------	--	--	--	--	--	--	---------

COT PP D. 110 MM; 30 GRD

17	SB17C1	82	BUCATA							59,00000
----	--------	----	--------	--	--	--	--	--	--	----------

COTURI PVC-U, PT.CANALIZARE, CU IMBINARE PRIN LIPIRE
LA 45;67 1/2;87 1/2 GRADE, AVIND D= 50 MM

18	8803078		BUCATA							20,00000
----	---------	--	--------	--	--	--	--	--	--	----------

COT HTB D50 45

Executanti02	Obiectiv013	Obi2	Cate1	4	5	ron
0	1	2	3			

19 8803079 BUCATA 8,00000

COT HTB D50 67 30'

20 8803081 BUCATA 15,00000

COT HTB D50 87 30'

21 8803076 BUCATA 8,00000

COT HTB D50 15

22 8803077 BUCATA 8,00000

COT HTB D50 30

23 00614C02 02 BUCATA 27,00000

COT /CONECTOR PP /TRIPLUS CU MUFA SI GARNITURA PT.
CANALIZARE INTERIOARA D. 40 MM

24 8803075 BUCATA 20,00000

COT HTB D40 87 30'

25 8803072 BUCATA 7,00000

COT HTB D40 45

26 00614F05 02 BUCATA 10,00000

RAMIFICATIE REDUSA PP /TRIPLUS /SILERE CU MUFA SI
GARNITURA PT.CANALIZARE INTERIOARA D. 110 MM

L:LA006X5-0005:8819090 -RAMIFICATIE REDUSA TRIPLUS D.110/50 45 GRD

27 00614E06 02 BUCATA 5,00000

RAMIFICATIE EGALA PP /TRIPLUS /SILERE CU MUFA SI G
ARNITURA PT.CANALIZARE INTERIOARA D.110 MM

L:LA006X5-0001:8810175 -RAMIFICATIE EGALA PP D. 110 /110 MM; 45 GRD

28 00614E03 02 BUCATA 5,00000

RAMIFICATIE EGALA PP /TRIPLUS /SILERE CU MUFA SI G
ARNITURA PT.CANALIZARE INTERIOARA D. 50 MM

L:LA006X2-0001:8810169 -RAMIFICATIE EGALA PP D. 50 /50 MM; 45 GRD



Executant02	Obiectiv013	Obi2	Cate1						[ron]
0	1	2	3	4	5				
29	SB21C1	82	BUCATA						3,00000

PIESA DE CURATIRE PVC-U, PT. CANALIZARE, CU IMBINARE
PRIN LIPIRE AVIND D=110 MM

30	SA39E	99	BUCATA						6,00000
----	-------	----	--------	--	--	--	--	--	---------

CAPAC DIN PVC PENTRU BUSONAREA PRIN LIPIRE A TEVIL
OR DIN PVC TIP GREU (G), D= 50MM

L:SL04F -0123:6715322 -CAPAC PVC PT. IMINARE PRIN LIP. DN 50 MM STAS 7177

31	SB22C1	82	BUCATA						18,00000
----	--------	----	--------	--	--	--	--	--	----------

REDUCTIE EXCENTRICA PVC-U, PT. CANALIZARE, CU IMBINAR
E PRIN LIPIRE, AVIND D= 50- 40 MM

32	SB44C1	82	BUCATA						3,00000
----	--------	----	--------	--	--	--	--	--	---------

SIFON DE PARDOSEALA DIN FONTA EMAILATA AVIND D= 50
MM, DUBLU CU 1 RACORD SI IESIRE LATERALA

33	8810541		BUCATA						2,00000
----	---------	--	--------	--	--	--	--	--	---------

AERATOR PP CU MEMBRANA D.50/75/110 MM

Cheltuieli directe

Alte cheltuieli directe

Contrib. asig. munca 2,2500%

TOTAL CHELT. DIRECTE

Cheltuieli indirecte Io = % x To

Profit Po = % x (To+Io)

TOTAL GENERAL pe categorie Vo = To+Io+Po

OFERTANT

Formular F3

OBIECTIV: 013 REABIL CENTR MEDIC DARMANESTI

LISTA

cu cantitatile de lucrari pe categorii de lucrari

Obiectul: 2 LUCRARI DE INSTALATII

Categoria de lucrari: 2 INST APA RECE/CALDA, TERMOFIC

Executant ⁰²	Obiectiv ⁰¹³	Obi ²	Cate ²	ron	
Nr. crt.	Capitolul de lucrari Simbol Denumire resursa Observatii Corectii Liste anexe	U. M.	Cantitatea	Pretul unitar a) materiale b) manopera c) utilaj d) transport Total(a+b+c+d)	Valoare
SECTIUNE TEHNICA			SECTIUNE FINANCIARA		
0	1	2	3	4	5
1	00611A01	02 M	228,00000		
TEAVA PP-R, PREGATIRE PT.MONTARE, MONTARE SI FIXAR E IN DISPOZITIVE DE SUSTINERE D.20 MM					
L:LA006J1-0079:8818560 -TEAVA PP-R ALBA PN20 SDR7,4 D. 20X2,8MM L=4 M					
2	00611A02	02 M	132,00000		
TEAVA PP-R, PREGATIRE PT.MONTARE, MONTARE SI FIXAR E IN DISPOZITIVE DE SUSTINERE D.25 MM					
L:LA006J1-0080:8818561 -TEAVA PP-R ALBA PN20 SDR7,4 D. 25X3,5MM L=4 M					
3	00611A03	02 M	20,00000		
TEAVA PP-R, PREGATIRE PT.MONTARE, MONTARE SI FIXAR E IN DISPOZITIVE DE SUSTINERE D.32 MM					
L:LA006J1-0081:8818562 -TEAVA PP-R ALBA PN20 SDR7,4 D. 32X4,4MM L=4 M					
4	RPIC53B	99 BUCATA	440,00000		
INLOC.SAU INTERCALAREA PE COND. PP,PP-R A FITINGUR ILOR (COTURI,MUFE,REDUCTII,DOPURI,ETC) CU D. 20 MM					
L:IL20B -0001:0003000 -APARAT DE SUDURA PRIN POLIFUZIUNE SI ELECTROFUZIUNE-COPRAX					
5	8818291	BUCATA	300,00000		
COT PP-R ALBA 90 GR PN20 SDR6 D.20					
6	8818285	BUCATA	50,00000		
COT PP-R ALBA 45 GR PN20 SDR6 D.20					
7	8808726	BUCATA	50,00000		
MUFA PP-R, D.20					

Executant02	Obiectiv013	Obi2	Cate2						(ron)
0	1	2	3	4	5				

8 8818303 BUCATA 40,00000

TEU PP-R ALBA PN20 SDR6 D. 20

9 RPIC53B 99 BUCATA 60,00000

INLOC.SAU INTERCALAREA PE COND. PP,PP-R A FITINGUR
ILOR (RACORDURI , COT DUBLU) CU D. 20 MM

10 8818281 BUCATA 50,00000

COT PP-R ALBA PN20 SDR6 D.20X1/2" FI

11 8812011 BUCATA 40,00000

RACORD COMPRESIUNE TIP FE D. 20 X 1/2"

12 8818243 BUCATA 10,00000

RACORD PP-R ALBA PN20 SDR6 D.20X1/2" FI

13 8818279 BUCATA 1,00000

COT PP-R ALBA PRINDERE PERETE PN20 SDR6 D.20X1/2"
FI

14 8804073 BUCATA 20,00000

CURBA OCOLIRE PESTE TEAVA PP (TXT)D.20

15 RPIC53C 99 BUCATA 300,00000

INLOC.SAU INTERCALAREA PE COND. PP,PP-R A FITINGUR
ILOR (COTURI,MUFE,REDUCTII,DOPURI,ETC) CU D. 25 MM

16 8818292 BUCATA 100,00000

COT PP-R ALBA 90 GR PN20 SDR6 D.25

17 8818286 BUCATA 30,00000

COT PP-R ALBA 45 GR PN20 SDR6 D.25

18 8818227 BUCATA 40,00000

MUFA PP-R ALBA PN20 SDR6 D. 25



Executant02	Obiectiv013	Obi2	Cate2						
0	1	2	3	4	5				[ron]

19 8818304 BUCATA 70,0000

TEU PP-R ALBA PN20 SDR6 D. 25

20 8818246 BUCATA 20,0000

RACORD PP-R ALBA PN20 SDR6 D.25X3/4" FI

21 8818255 BUCATA 10,0000

RACORD PP-R ALBA PN20 SDR6 D.25X3/4" FE

22 8808741 BUCATA 10,0000

CURBA OCOLIRE PP-R, D.25

23 8818261 BUCATA 20,0000

REDUCTIE PP-R ALBA PN20 SDR6 D. 25/20

24 RPIC53D 99 BUCATA 78,0000

INLOC.SAU INTERCALAREA PE COND. PP,PP-R A FITINGUR
ILOR (COTURI,MUFE,REDUCTII,DOPURI,ETC) CU D. 32 MM

25 8818293 BUCATA 16,0000

COT PP-R ALBA 90 GR PN20 SDR6 D.32

26 8818228 BUCATA 8,0000

MUFA PP-R ALBA PN20 SDR6 D. 32

27 8818316 BUCATA 14,0000

TEU REDUS PP-R ALBA PN20 SDR6 D.32/25/32

28 8818314 BUCATA 12,0000

TEU REDUS PP-R ALBA PN20 SDR6 D.32/20/32

29 8808716 BUCATA 10,0000

REDUCTIE PP-R, 32/20

Executant02	Obiectiv013	Obi2	Cate2							ron
0	1	2	3	4	5					

30 8808717 BUCATA 10,00000

REDUCTIE PP-R, 32/25

31 8818247 BUCATA 4,00000

RACORD PP-R ALBA PN20 SDR6 D.32X1" FI

32 8818256 BUCATA 4,00000

RACORD PP-R ALBA PN20 SDR6 D.32X1" FE

33 RPID02B 91 BUCATA 36,00000

ROBINETI SAU FITINGURI CU DIAMETRUL PINA LA 1"

34 8810583 BUCATA 26,00000

ROBINET INCHIDERE COLTAR 1/2"

35 3271349 BUCATI 6,00000

ROBINET CU BILA D=22

36 2000115 BUCATI 4,00000

ROBINET DE INCHIDERE CU BILA D=16

37 RPGA18G 99 BUCATA 24,00000

INTERCALARE TEU ,COT,NIPLU,RED. DIN ALAMA

38 8801498 BUCATA 10,00000

NIPLU ALAMA 1/2"

39 8801499 BUCATA 10,00000

NIPLU ALAMA 3/4"

40 8812828 BUCATA 4,00000

REDUCTIE ALAMA FEFI 1" 3/4"

Executanti02	Obiectiv013	Obi2	Cate2						
0	1	2	3	4	5				
41	IA23A	99	BUCATA						3,00000

FILTRU DE COMBUSTIBIL LICHID

42	8815350		BUCATA						1,00000
----	---------	--	--------	--	--	--	--	--	---------

FILTRU MAGNETIC ANTICALCAR 1/2"

43	8801405		BUCATA						2,00000
----	---------	--	--------	--	--	--	--	--	---------

FILTRU IMPURITATI 1/2

44	IZH01XA	91	M						372,00000
----	---------	----	---	--	--	--	--	--	-----------

IZOLAREA CONDUCTELOR D=22-35 MM

45	7805328		M						220,00000
----	---------	--	---	--	--	--	--	--	-----------

IZOLATIE TERMICA K-FLEX (BARA 2 M) 9 X 22 MM

46	7805329		M						132,00000
----	---------	--	---	--	--	--	--	--	-----------

IZOLATIE TERMICA K-FLEX (BARA 2 M) 9 X 28 MM

47	7805330		M						20,00000
----	---------	--	---	--	--	--	--	--	----------

IZOLATIE TERMICA K-FLEX (BARA 2 M) 9 X 35 MM

48	SC07E1	82	BUCATA						11,00000
----	--------	----	--------	--	--	--	--	--	----------

LAVOAR DIN PORTELAN SANITAR, MONTAT PE PIEDESTAL

L:11402 -0008:2442276 -LAVOAR PORTELAN F SPATAR L 2-600MM MONOCOL C1 S 1540
L:11404 -0002:2453835 -PIEDESTAL LAVOAR P1 PORTELAN MONO C. 1 NI 806

49	SD06A1	82	BUCATA						11,00000
----	--------	----	--------	--	--	--	--	--	----------

BATERIE AMESTECATOARE, STATIVA, PENTRU LAVOAR AVIND
D=1/2 TOLI

L:11413 -0017:4201353 -BATERIE AMEST. LAVOAR FONTA 1/2" EMAIL. STATIVA S8732

50	SC31A1	82	BUCATA						11,00000
----	--------	----	--------	--	--	--	--	--	----------

VENTIL DE SCURGERE TIP...

L:11410 -0006:4203337 -VENTIL SCURGERE LAVOAR, SPALATOR 1" CU RACORD S9610

Executant02	Obiectiv013	Obi2	Cate2						[ron]
0	1	2	3	4	5				

51 SC07B 99 BUCATA 4,00000

VAS CLOSET COMPLET ECHIPAT, PORTELAN ETC., REZERVOR
MONT.LA INALTIME; SEMIINALTIME, SIFON TIP S

L:SL12D -0025:672018F -TUB FARA MUFA, POLIPROPILENA IGNIFUGA., D110, L5000MM
L:SL25E -0001:2949482 -RAMA VAS CLOSET PLACAJ FAG TIP B C.2 CU CAPAC S 3489
L:SL29 -0003:2442757 -VAS CLOSET COL2-A PORTELAN ALB C. 1 S 2066
L:SL30 -0001:2452958 -REZERVOR WC R 2 SEMIINALTIME ALB C.1 S 9441

52 SC03A1 82 BUCATA 1,00000

CABINA PENTRU DUS

53 SD04A1 82 BUCATA 1,00000

BATERIE AMESTEC CU DUS FIX DE 1/2 TOLI, DIN FONTA S
AU ALAMA, MONT CU DIBL.LEMN PE ZID DE CARAMIDA

L:11413 -0005:4201523 -BATERIE AMEST.ALAMA TUB FLEXIBPARA DUS A 1/2 NI 4309

54 SC26A2 82 BUCATA 11,00000

OGLINDA SANIT.SEMICRIST.MARGINI.SLEF.CU DIMENS.500
X600MM

55 SC24A1 82 BUCATA 1,00000

PORTPROSOP DIN AM NICHEL.MONT.PE PERETI TIP U, CU 1
BRAT, DESCHID.450MM

56 SC30A1 82 BUCATA 4,00000

SUPORT PT.HIRTIE CALITATEA 1 (PORTHIRTIE) DIN PORT
ELAN SANITAR, HA1 NI 545/63

Cheltuieli directe

Alte cheltuieli directe

Contrib. asig. munca 2,2500%

TOTAL CHELT. DIRECTE

Cheltuieli indirecte Io = % x To

Profit Po = % x (To+Io)

TOTAL GENERAL pe categorie Vo = To+Io+Po

OFERTANT

Formular F3

OBIECTIV: 013 REABIL CENTR MEDIC DARMANESTI

LISTA

cu cantitatile de lucrari pe categorii de lucrari

Obiectul: 2 LUCRARI DE INSTALATII

Categoria de lucrari: 3 INSTALATII TERMICE

Executant02	Obiectiv013	Obi2	Cate3				ron
Nr. crt.	Capitolul de lucrari Simbol Denumire resursa Observatii Corectii Liste anexe	U. M.	Cantitatea	Pretul unitar a) materiale b) manopera c) utilaj d) transport Total(a+b+c+d)	Valoare		

SECTIUNE TEHNICA

SECTIUNE FINANCIARA

0	1	2	3	4	5
---	---	---	---	---	---

1	IA01A1	82 BUCATA	1,00000		
---	--------	-----------	---------	--	--

MONTARE CENTRALA TERMICA PE GAZ

2	8800601	BUCATA	1,00000		
---	---------	--------	---------	--	--

CENTRALA RBA 35 GAZ

3	FF10A1	82 BUCATA	1,00000		
---	--------	-----------	---------	--	--

REGULATOR DE PRESIUNE PT.NM3, DN 20-25

4	7337738	BUCATA	1,00000		
---	---------	--------	---------	--	--

REGULATOR PRESIUNE PT.GAZE, DEBIT 20 MC/H, RACORD 1-1"

5	IB19A1	82 BUCATA	1,00000		
---	--------	-----------	---------	--	--

RACORDAREA CENTRALEI LA GAZ

6	00802B17A1	02 BUCATA	1,00000		
---	------------	-----------	---------	--	--

MONTAJ DETECTOARE DE GAZ PENTRU MEDIU NORMAL

L: LA008C2-0016:7801015 -DETECTOR DE GAZ

7	FE13B1	82 BUCATA	4,00000		
---	--------	-----------	---------	--	--

ROBINET DE TRECERE 1/2-3/4

8	IA30A1	82 BUCATA	1,00000		
---	--------	-----------	---------	--	--

FILTRU DE COMBUSTIBIL LICHID- MAGNETIC DE 3/4"

Executant02	Obiectiv013	Obi2	Cate3		[ron]
0	1	2	3	4	5
9	IB06B	99 BUCATA			21,00000

MONTARE RADIATOARE DIN OTEL

10	5709080	BUCATA			12,00000
----	---------	--------	--	--	----------

RADIATOR DIN OTEL TIP PANOU 22- H=600 SI L=1200

11	5709082	BUCATA			2,00000
----	---------	--------	--	--	---------

RADIATOR DIN OTEL TIP PANOU 22- H=600 SI L=1400

12	5709083	BUCATA			2,00000
----	---------	--------	--	--	---------

RADIATOR DIN OTEL TIP PANOU 22- H=600 SI L=1600

13	5709084	BUCATA			1,00000
----	---------	--------	--	--	---------

RADIATOR DIN OTEL TIP PANOU 22- H=600 SI L=1800

14	5709331	BUCATA			3,00000
----	---------	--------	--	--	---------

RADIATOR DIN TEAVA DE OTEL PT BAIE CU H=1200MM L=500MM

15	5709357	BUCATA			1,00000
----	---------	--------	--	--	---------

RADIATOR DIN TEAVA DE OTEL PT BAIE CU H=1475MM L=600MM

16	RPID02B	91 BUCATA			4,00000
----	---------	-----------	--	--	---------

ROBINETI COLTAR PENTRU RADIATOARE

17	RPID02B	91 BUCATA			15,00000
----	---------	-----------	--	--	----------

ROBINETI COLTAR CU TERMOSTAT

18	FG02A1	82 BUCATA			1,00000
----	--------	-----------	--	--	---------

MONTARE TERMOSTAT AMBIENT

Cheltuieli directe

Alte cheltuieli directe

Contrib. asig. munca 2,2500%

TOTAL CHELT. DIRECTE

Cheltuieli indirecte Io = % x To

Formular F3

<i>Executanti</i> 02	<i>Obiectiv</i> 013	<i>Obi</i> 2	<i>Cate</i> 3						[ron]
0	1	2	3				4	5	
Profit		Po =	% x (To+Io)						
TOTAL GENERAL pe categorie		Vo = To+Io+Po							

OFERTANT

Formular F3

OBIECTIV: 013 REABIL CENTR MEDIC DARMANESTI

LISTA

cu cantitatile de lucrari pe categorii de lucrari

Obiectul: 2 LUCRARI DE INSTALATII

Categoria de lucrari: 4 INSTALATII ELECTRICE

Nr. crt.	Capitolul de lucrari Simbol Denumire resursa Observatii Corectii Liste anexe	U. M.	Cantitatea	Pretul unitar a) materiale b) manopera c) utilaj d) transport Total(a+b+c+d)	Valoare
SECTIUNE TEHNICA			SECTIUNE FINANCIARA		
0	1	2	3	4	5
1	EF01B1 82 BUCATA		1,00000		

TABLOU ELECTRIC METALIC 60X40X20CM, IP56

L:12061 -0017:7348841 -TABLOU DISTRIB.PLACA MARMURA 600X400X30MM 2CIRC.350A

2	W1A01XA1 93 BUCATA		14,00000		
---	--------------------	--	----------	--	--

INTRERUPATOR AUTOMAT TRIPOLAR CU ULEI MONT.INT.TIP
:IUP-10-20KV (630,1000)A,CU MR (1-2)

3	W1A01XA1 93 BUCATA		2,00000		
---	--------------------	--	---------	--	--

INTRERUPATOR AUTOMAT MODULAR IK 60

4	W3D11A 99 BUCATA		4,00000		
---	------------------	--	---------	--	--

DESCARCATOR TUBULAR

5	EB04A 99 M		1500,00000		
---	------------	--	------------	--	--

CONDUCTOR DE CUPRU MYF 1X2.5

L:EL11 -0191:4829040 -CONDUCTOR MYF 2,5 S 9108

6	EB04A 99 M		1500,00000		
---	------------	--	------------	--	--

CONDUCTOR DE ALUMINIU SAU CUPRU, IZOLAT, INTRODUS I
N CANALETI-PLINTE,AVAND SECTIUNEA <= 1 MMP

L:EL11 -0190:4829026 -CONDUCTOR MYF 1,5 S 9108

7	EB04A 99 M		15,00000		
---	------------	--	----------	--	--

CONDUCTOR DE CUPRU MFY, 1X16

L:EL11 -0195:4829088 -CONDUCTOR MYF 16 S 9108
L:EL12 -0027:7309546 -CLEME LEGATURA 16 MMP 660V 63A ST 4002/14 SIMB.511

Executant02	Obiectiv013	Obi2	Cate4						[ron]
0	1	2	3	4	5				

8 **EB04A** 99 M 105,00000

CONDUCTOR DE CUPRU MYF 1X6

L:EL11 -0193:4829064 -CONDUCTOR MYF 6 S 9108
L:EL12 -0026:7309534 -CLEME LEGATURA 6 MMP 660V 31,5A ST.4002/14 SIMB.510

9 **EA13A2** 82 M 600,00000

TUB IZOLANT USOR PROTEJAT FLEXIBIL IPFY CU INVELIS
FLEXIBIL DIN MATERIAL PLASTIC CU D=15 MM.

10 **EA13A3** 82 M 700,00000

TUB IZOLANT USOR PROTEJAT FLEXIBIL IPFY CU INVELIS
FLEXIBIL DIN MATERIAL PLASTIC CU D=20 MM.

11 **EA13B1** 82 M 75,00000

TUB IZOLANT USOR PROTEJAT FLEXIBIL IPFY CU INVELIS
FLEXIBIL DIN MATERIAL PLASTIC CU D=25 MM.

12 **W3K04A1** 82 M 4,00000

CANAL CABLU 40X60MM

13 **EA16C** 99 BUCATA 56,00000

DOZA DE DERIVATIE, PT.CABLURI SAU TEVI DE INSTAL.,
IN MEDIU NORMAL, TIP NBU-PG 16; NBU-PG 21

L:EL03H -0008:7319034 -DOZA PATRATA

14 **ED01A1** 82 BUCATA 20,00000

INTRERUPATOR MANUAL INGROPAT UNIPOLAR CONSTRUCTIE
NORMALA SAU IMPERMEABILA *

L:12010 -0019:5500732 -INTRERUPTOR CUMPARA PT.SIMBOL 0186 250V 10A

15 **ED08A1** 82 BUCATA 74,00000

PRIZA MONTATA INGROPAT CONSTR.NORMALA IMPERMEABILA
SAU NORMALA CU CONTACT PROTECTIE

L:12017 -0002:5536169 -PRIZA MONOBLOC SUB TENCUIALA 250/10A COD 160

16 **ED08D1** 82 BUCATA 6,00000

MONTAT PRIZE DATE RJ45, CAT 5E

17 **ED03E1** 82 BUCATA 4,00000

INTRERUPATOR CAP SCARA, INCASTRAT, MODULAR

Executant02	Obiectiv013	Obi2	Cate4						ron
0	1	2	3	4	5				

18 W1R06A1 82 M 12,00000

ELECTROD DIN TEAVA DE OTEL DE DOI TOLI SI JUMATATE
PENTRU LEGAREA LA PAMINT IN TEREN NORMAL

19 RCLP01A 02 M 20,00000

IMBUNATATIREA UNEI PRIZE DE PUNERE LA PAMANT PRIN
PLATBANDA ZINCATA IN PAMANT TEREN NORMAL

20 EG10A1 82 BUCATA 1,00000

CUTIE CU ECLISA DE LEGATURA PT.CENTURA DE INPAMINT
ARE

21 ATD12A 82 M 305,00000

CABLU MASURA, CDA, SEMNALIZARE POZAT & N TUBURI CU:PI
NA LA 10 FIRE CONDUCTOARE DE 1,5-2,5MMP

22 IB09A01 82 BUCATA 13,00000

PANOU LED , 40W, 60X60CM, IP20

23 1000310 BUCATI 13,00000

PANOU LED, 40 W, 3600 LM, 60X60CM, IP20, LUMINA RE
CE

24 EE10A1 82 BUCATA 8,00000

CORP DE ILUMINAT LA EXTERIOR

L:12009 -0012:5102554 -CORP IL.FL.FIA -01 140 220V 1X 40W CS

25 00803C08B1 02 BUCATA 2,00000

MONTAJ CAMERE VIDEO DE SUPRAVEGHERE, IN CARCASA, C
AMERE VIDEO SPEED-DOME DE INTERIOR

L:LA008D9-0001:7801092 -CAMERA VIDEO DE SUPRAVEGHERE,SPEED-DOME INT/EXT, TIP C1

26 00803C08B2 02 BUCATA 6,00000

MONTAJ CAMERE VIDEO DE SUPRAVEGHERE, IN CARCASA, C
AMERE VIDEO SPEED-DOME DE EXTERIOR

L:LA008D9-0002:7801093 -CAMERA VIDEO DE SUPRAVEGHERE,SPEED-DOME INT/EXT, TIP C2

27 1000311 BUCATI 1,00000

UNITATE NVR

Executant02	Obiectiv013	Obi2	Cate4	[ron]	
0	1	2	3	4	5
28	1000312	BUCATI	1,00000		

UNITATE HDD

29	1000313	BUCATI	4,00000		
----	---------	--------	---------	--	--

SWITCH INTERNET 8 PORTURI

Cheltuieli directe

Alte cheltuieli directe

Contrib. asig. munca 2,2500%

TOTAL CHELT. DIRECTE

Cheltuieli indirecte Io = % x To

Profit Po = 1% x (To+Io)

TOTAL GENERAL pe categorii Vo = To+Io+Po

OFERTANT

Formular F3

OBIECTIV: 013 REABIL CENTR MEDIC DARMANESTI

LISTA

cu cantitatile de lucrari pe categorii de lucrari

Obiectul: 2 LUCRARI DE INSTALATII

Categoria de lucrari: 5 INSTALATII DE DETECTIE

Executant02	Obiectiv013	Obi2	Cate5	ron	
Nr. crt.	Capitolul de lucrari Simbol Denumire resursa Observatii Corectii Liste anexe	U. M.	Cantitatea	Pretul unitar a) materiale b) manopera c) utilaj d) transport Total(a+b+c+d)	Valoare
SECTIUNE TEHNICA			SECTIUNE FINANCIARA		
0	1	2	3	4	5
1	00802B02A2 02 BUCATA		1,00000		

CENTRALA DETECTARE / AVERTIZARE INCENDIU "CONVENTI
ONALA" 4-24 ZONE, MONT PE PERETE GIPSCARTON

L:LA008A4-0005:7800937 -ACUMULATOR CU GEL 12V- 26AH -REZIST.LA FOC, 166X175X125
L:LA008C1-0002:1800996 -CENTRALA INCENDIU CONVENTIONALA MAX 24 ZONE

2	00802B02C1 02 BUCATA		1,00000		
---	----------------------	--	---------	--	--

CENTRALA DETECTARE / AVERTIZARE INCENDIU "CONVENTI
ONALA" 4-24 ZONE - VERIFICARI / PROBE

3	00802B10A2 02 BUCATA		25,00000		
---	----------------------	--	----------	--	--

MONTAJ DETECTOARE "CONVENTIONALE" DE FUM, TEMP, CO
MBIN (FUM+ TEMP) PE TAVAN DE GIPSCARTON

L:LA008C2-0001:7801000 -DETECTOR CONVENTIONAL DE FUM

Cheltuieli directe

Alte cheltuieli directe

Contrib. asig. munca 2,2500%

TOTAL CHELT. DIRECTE

Cheltuieli indirecte Io = % x To

Profit Po = % x (To+Io)

TOTAL GENERAL pe categorie Vo = To+Io+Po

OFERTANT